

L I M I T E D T E N D E R  
N O T I C E

Tender Ref. No.

Date Tender Due Date

MAINT/40/2021-CIVIL SMR CHE-SMR CHE DEPTT-11775

10-08-2021

27-08-2021

To

Dear Sir,

The Purchase Officer, SAMEER-Centre for Electromagnetics invites sealed tender for the supply of materials / Services as per details given below:

Sl. No	Description of Items
1.	Rectification of storm drain at EDC, Perungudi, Chennai (Schedule of Quantities Attached)

**Terms and Conditions:**

1. Tenders to be submitted to The Purchase Officer ,SAMEER-CEM ,CIT Campus,2<sup>nd</sup> Cross Road, Taramani, Chennai 600 113.
2. Delivery / Completion period should be clearly indicated.
3. Excise Duty, GST Percentage should be clearly indicated if admissible. Not eligible for FORM 'C' /'D'
4. WE ARE EXEMPTED FROM EXCISE DUTY
5. Quotation should be valid for atleast 60 days from the date of opening of the tender
6. Quotation should be sent in sealed envelope super scribing the tender reference number and tender due date. E-mail quotation will not be accepted. YOUR OFFER WILL NOT BE CONSIDERED IF OUR TENDER REFERENCE NO. & TENDER DUE DATE IS NOT MENTIONED ON COVER.
7. Late tenders will not be accepted under any circumstances
8. We reserve the right to accept or reject any quotations fully or partly without assigning any reasons.
9. For Further Clarification Please Contact 044-22544061 / 22544020 Email: [purchase.chn.sameer@nic.in](mailto:purchase.chn.sameer@nic.in)
10. Unsolicited bids shall not be considered

  
(P. Ramamoorthi)  
Head – Administration

Contd.,



CIT Campus, 2<sup>nd</sup> Cross Road, Taramani, Chennai - 600 113, India

सी.आई.टी.परीसर, दूसरा क्रॉस रोड, तारामणी चेन्नै - ६०० ११३.

दूरध्वनि : Tel : +91-44-22541583 / 1817 / 2106 / 2452 फैक्स / Fax : 2254 1938 / 1424

वेबसाइट : [www.sameer.org.in](http://www.sameer.org.in)

NAME OF WORK: **Rectification of storm drain at EDC, Perungudi, Chennai**

**SCHEDULE OF QUANTITIES**

Sl.No	Description of item	Qty	Unit
1.	Existing damaged storm water drain dismantling and clearing of the debris and disposing the same all as per the direction and instruction of Engineer In Charge.	6	Cum
2.	Providing and laying of Plain cement concrete of 1:2:4 using 25mm maximum size graded aggregate for storm drain bottom including ramming,, compaction, leveling, curing, including all materials and Labor. etc all as per the direction and instruction of Engineer In Charge.	1	Cum
3.	Providing and laying of reinforced cement concrete of 1:2:4 using 25mm maximum size graded aggregate including ramming, compaction, leveling, curing, for plinth beam on both sides of size 300x250 mm necessary reinforcement and form works etc complete. all as per the direction and instruction of Engineer In Charge.	3	Cum
4.	Providing and constructing 230 mm brick masonry using well burnt table molded bricks in CM 1:6 for the storm rain walls including curing, racking our the joints etc complete. all as per the direction and instruction of Engineer In Charge	4	Cum
5.	Providing plastering works to the brick works in CM 1:4 20mm thick including curing, forming grooves wherever required etc complete. all as per the direction and instruction of Engineer In Charge	40	Sqm