

L I M I T E D T E N D E R
N O T I C E

Tender Ref. No.

Date

Tender Due Date

EST-11/11/2019-DSPD_SAM_CHENNAI-8621

14-08-2020

31-08-2020

To

Dear Sir,

The Purchase Officer, SAMEER-Centre for Electromagnetics invites sealed tender for the supply of materials as per details given below:

Sl.No	Description of Items	Qty No.s
1	Re-establishment of pond in the lawn at Taramani Campus (Schedule of Quantities Attached)	40

Terms and Conditions

1. Price quoted should be on the basis of Destination delivery at Taramani Campus, Chennai 600 113.
2. Delivery / Completion period should be clearly indicated.
3. Excise Duty, GST Percentage should be clearly indicated if admissible. Not eligible for FORM 'C' / 'D'
4. WE ARE EXEMPTED FROM EXCISE DUTY
5. Quotation should be valid for atleast 60 days from the date of opening of the tender
6. Quotation should be sent in sealed envelope super scribing the tender reference number and tender due date.
YOUR OFFER WILL NOT BE CONSIDERED IF OUR TENDER REFERENCE NO. &
TENDER DUE DATE IS NOT MENTIONED ON COVER.
7. Late tenders will not be accepted under any circumstances
8. We reserve the right to accept or reject any quotations fully or partly without assigning any reasons.
9. For Further Clarification Please Contact 044-22544061 / 22544020 Email: purchase.chn.sameer@nic.in
10. Unsolicited bids shall not be considered

P. Ramamoorthi
14/8/2020
(P.Ramamoorthi)
Head – Administration
Contd..



ELECTRONICS INDIA

Million Needs, Million Chops.

CIT Campus, 2nd Cross Road, Taramani, Chennai - 600 113, India

सी.आई.टी.परीसर, दूसरा क्रॉस रोड, तारामणी चेन्नै - ६०० ११३.

दूरवार्ता : Tel : +91-44-22541583 / 1817 / 2106 / 2452 फैक्स / Fax : 2254 1838 / 1424

वेबसाईट / web: <http://www.sameer.gov.in> ई-मेल / E-mail : pd@cern.sameer.gov.in

NAME OF WORK: Re-establishment of the pond in the lawn
at Taramani Campus, Chennai 600 113

SCHEDULE OF QUANTITIES

Sl.No:	Description of item	Qty	Unit
1.	<p>Removal of the existing plaster from the surfaces of the wall, top surface and from the floorings etc all as per the direction and instruction of Engineer In Charge., Plastering the walls, top surfaces, floor with DR. Fixit Predefine cement base chemical two times, plastering all the surfaces smoothly and giving a neat finish by using polymer and providing U-V epoxy coating two times for all the plastered surface. etc all as per the direction and instruction of Engineer In Charge. The leak test for the pond to be performed. Guarantee : For 2 years. Payment : Payment will be released on successful completion of the water leak test</p>	40	Sqm